BID SUBMISSION PACKAGE

CCB First Floor Door Widening

Pierce County Solicitation 2026-SWR-031

Project Location	County-City Building, 930 Tacoma Ave S, Tacoma, WA 98402
Owner	Pierce County
Project / Contract	Project No. 24-00013 / Contract No. SC-2026-SWR-031
Bid Due	May 20, 2026 at 1:00 PM
Prepared By	[Company Legal Name] / KNB LLC - to be confirmed before submission
Prepared Date	May 6, 2026
Bid Amount	$_____
Authorized Signer	_____, _____

Submission note: This single PDF is a consolidated professional bid package. If Pierce County/OpenGov requires official forms, bid bond, certifications, background checks, or addenda acknowledgments as separate required uploads, those official documents must still be completed exactly as required by the owner.

Table Of Contents

1. Bid Cover Letter
2. Scope And Price Proposal
3. Construction Schedule And Work Plan
4. Quality Control Plan
5. Site Safety And Logistics Plan
6. Prevailing Wage And Compliance Plan
7. Background Check Roster
8. ACM Statement Of Compliance
9. Submission Checklist
10. Final Submission Instructions

Original owner-issued documents reviewed for this package include the bid packet, drawings, technical specifications, Division 01 general requirements, background check form, hazardous material survey, hot work procedure, and sample ACM compliance form.

Bid Cover Letter

[Company Letterhead] [Company Legal Name] [Address] [Phone] [Email] [Washington Contractor License No.] [UBI No.]

May [__], 2026

Pierce County Procurement & Contract Services Attn: Dalton Gamboa 930 Tacoma Ave S Tacoma, WA 98402

Re: Bid Submission - CCB First Floor Door Widening, Solicitation 2026-SWR-031

Dear Pierce County Procurement Team,

[Company Legal Name] is pleased to submit our bid for the CCB First Floor Door Widening project at the County-City Building, 930 Tacoma Ave S, Tacoma, Washington.

We understand this project is located in an active public facility and requires careful coordination, clean daily work practices, public-area protection, background-screened personnel, and strict compliance with Washington public works requirements. Our bid is based on the issued bid packet, technical specifications, drawings, hazardous materials survey, and all addenda acknowledged in the official bid form.

Our proposed work includes selective demolition, protection and salvage of existing finishes, cold-formed metal framing, hollow metal frames, 90-minute fire-rated glazing, Type X gypsum board assemblies, Level 5 finishing where required, reinstallation/coordination of granite and terrazzo elements, stainless steel trim/protection, sealants, acoustic ceiling repair, cleanup, and closeout coordination.

We will comply with applicable Washington State prevailing wage requirements, background check requirements, site safety requirements, and all owner security/logistics procedures. We will coordinate closely with Pierce County, the architect, inspectors, and affected building stakeholders to limit disruption to public operations.

Bid amount: $[_____] Addenda acknowledged: [List addenda numbers/dates] Authorized signer: [Name, Title]

Respectfully submitted,

Signature: _____ Printed Name: [_____] Title: [_____] Company: [_____] Date: [_____]

Scope And Price Proposal

Project: CCB First Floor Door Widening Location: County-City Building, Tacoma, WA Bid due: May 20, 2026, 1:00 PM

Base Bid Scope

The base bid includes labor, materials, equipment, supervision, coordination, and closeout necessary to complete the first-floor door widening work shown in the bid documents.

Included work:

- Project mobilization, site protection, and daily cleanup.
- Coordination with Pierce County security, building operations, architect, and inspectors.
- Selective demolition in the first-floor lobby/work area.
- Salvage, protection, storage, and reinstallation/coordination of designated existing granite/terrazzo finishes where required by drawings/specifications.
- Removal/rework of existing GWB, stainless trim, ceiling components, and related finishes in the affected work area.
- Cold-formed metal framing and required anchorage.
- Type X gypsum board, cementitious backer board where required, taping, finishing, and paint-ready Level 5 surfaces where specified.
- Hollow metal frames meeting specified fire-rating and SDI requirements.
- Fire-rated glazing system, including 90-minute-rated glass matching specified basis of design or approved equivalent.
- Stainless steel trim/protection at modified openings as required.
- Sealants, acoustic sealant, perimeter sealing, and finish transitions.
- Acoustic ceiling repair/reinstallation to match existing conditions.
- Final cleaning, punch list, and closeout documents.

Exclusions / Clarifications

These items should be clearly confirmed before bid submission:

- Work outside the documented first-floor lobby/door widening limits.
- Hazardous material abatement beyond the issued survey. The survey indicates no asbestos detected in tested samples and no lead detected in tested paint samples; unknown materials discovered later should be handled under owner direction.
- Structural steel or concealed structural repairs not shown in the bid documents.
- After-hours work unless required by owner/security constraints or later addendum.
- Utility relocation beyond items specifically shown in drawings.
- Permit fees unless expressly assigned to contractor in the bid packet.
- Sales tax treatment to follow bid instructions and Pierce County requirements.

Pricing Worksheet

Use this as an estimating worksheet. Final bid should use the owner-issued bid form.

Cost Item	Low Planning Range	High Planning Range	Final Quote
Mobilization, supervision, project management	$6,000	$10,000	$
Site protection, temporary barriers, dust/noise controls	$3,500	$7,500	$
Selective demolition and disposal	$5,000	$8,500	$
Cold-formed metal framing / rough carpentry	$8,000	$13,000	$
Hollow metal frames / fire-rated frame scope	$7,000	$14,000	$
90-minute fire-rated glazing	$15,000	$28,000	$
GWB, CBB, taping, Level 5 finish, painting prep	$10,000	$18,000	$
Granite/terrazzo salvage and reinstall coordination	$8,000	$16,000	$
Stainless trim/protection	$6,000	$12,000	$
Acoustic ceiling repair	$4,000	$8,000	$
Sealants/fire/acoustic perimeter details	$2,500	$5,500	$
Prevailing wage premium / payroll compliance allowance	$8,000	$18,000	$
Bond/insurance/admin/compliance	$3,000	$7,000	$
Contingency / procurement risk	$7,500	$15,000	$
Total planning range	$93,500	$180,500	$

Recommended Bid Position

Do not bid at the published budget simply because it is listed. Price from quotes and labor plan. The largest risk items are fire-rated glazing, hollow metal frames, downtown Tacoma logistics, prevailing wage labor, and preserving/reinstalling existing finishes.

Before final submission, obtain hard quotes for:

- Pilkington Pyrostop or approved fire-rated glazing system.
- Hollow metal frames and anchors/fire-rating labels.
- Stainless steel trim.
- Granite/terrazzo handling.
- Any after-hours premium requested by building operations.

Construction Schedule And Work Plan

Contract duration: 42 calendar days from Notice to Proceed, plus 5 calendar days for final completion if allowed by contract.

Schedule Summary

Phase	Target Days	Work
Preconstruction	Days 1-7	Submittals, background checks, material procurement, site logistics, confirmation of field dimensions.
Mobilization / protection	Days 8-10	Protection, access controls, temporary barriers, dust control, delivery staging.
Selective demolition	Days 11-14	Remove affected finishes, salvage designated granite/terrazzo/stainless items, expose conditions.
Framing / rough work	Days 15-21	Cold-formed metal framing, anchorage, rough opening verification, ceiling support adjustments.
Frames / glazing coordination	Days 18-30	Hollow metal frame installation, fire-rated glazing coordination, field verification, inspections.
GWB / CBB / finish base	Days 22-32	Type X GWB, CBB where required, taping, Level 5 finish in visible areas.
Finish restoration	Days 30-38	Granite/terrazzo reinstall, stainless trim, sealants, acoustic ceiling repair, paint-ready completion.
Punch / closeout	Days 39-42	Owner/architect punch, cleaning, labels, documents, closeout.
Final completion	Days 43-47	Final punch resolution, if required.

Work Approach

1. Confirm all field dimensions before ordering final glazing and frame components. 2. Treat the public lobby as an occupied facility work zone. 3. Maintain clean access routes and protect adjacent finishes daily. 4. Coordinate noisy/dust-producing work with Pierce County building operations. 5. Preserve existing granite/terrazzo elements marked for reuse. 6. Verify fire-rated assembly requirements before covering work. 7. Document concealed conditions with photos before proceeding. 8. Complete closeout with product data, inspection records, and punch completion.

Procurement Priority

Order or reserve these immediately after award:

- Fire-rated glazing.
- Hollow metal frames.
- Stainless steel trim.
- Specialty sealants.
- Matching ceiling tile/grid components.

Quality Control Plan

Purpose

This plan describes how the contractor will control quality for a public-building interior door widening project involving fire-rated glazing, hollow metal frames, cold-formed metal framing, gypsum assemblies, existing finish restoration, stainless trim, sealants, and ceiling repair.

QC Responsibilities

Role	Responsibility
Project manager	Submittals, schedule, owner/architect coordination, change control.
Superintendent / lead	Daily field quality, layout, protection, sequencing, photo records.
Trade leads	Workmanship, product compliance, installation instructions, inspections.
Authorized signer	Certifications, compliance documents, final acceptance.

Inspection Hold Points

- Before demolition: photo-document existing conditions and protection.
- After selective demolition: verify concealed conditions, dimensions, substrate, and conflicts.
- Before frame/glazing order release: verify rough opening dimensions.
- Before closing walls: verify framing, anchorage, backing, fire/acoustic perimeter conditions.
- Before finish install: verify GWB finish level, substrate flatness, and transitions.
- Before final inspection: verify glazing labels, frame labels, sealants, stainless finish, ceiling match, cleanup.

Product Compliance

Fire-rated glazing:

- Use specified basis-of-design product or approved equal only.
- Confirm rating, safety glazing requirements, thickness, labeling, and compatible frame system.
- Keep manufacturer data and installation instructions in closeout file.

Hollow metal frames:

- Confirm gauge, rating, anchors, labels, and prep.
- Protect primer/finish until final acceptance.

Gypsum / CBB / finishes:

- Use Type X gypsum where specified.
- Finish visible GWB surfaces to specified level.
- Use compatible backing for granite/terrazzo/tile areas.

Sealants:

- Use specified or approved sealants.

- Confirm joint prep, primer need, backing, tooling, and color match.

Existing finishes:

- Salvage and reinstall only pieces approved for reuse.
- Protect edges and surfaces from chips, stains, and scratches.

Closeout Records

- Product data and approved submittals.
- Fire-rated glazing/frame documentation.
- Daily photo log.
- Inspection/punch list records.
- Final cleaning confirmation.
- Warranty information if required.

Site Safety And Logistics Plan

Project Context

The work is inside the County-City Building at 930 Tacoma Ave S, Tacoma, WA. The building is an active public facility. Safety planning must protect workers, county staff, visitors, existing finishes, and public circulation.

Site Access

- All workers must complete required background checks before entering controlled work areas.
- Workers must follow Pierce County sign-in, badge, escort, and access rules.
- Deliveries must be coordinated with building operations.
- Parking/loading limitations in downtown Tacoma must be confirmed during the pre-bid walkthrough.

Public Protection

- Install temporary barriers and signage approved by the owner.
- Maintain clean and code-compliant paths of travel.
- Keep tools, cords, materials, and debris inside the controlled work area.
- Protect floors, walls, granite, terrazzo, stainless, ceiling, and lobby finishes.
- Maintain daily cleanup before leaving site.

Dust, Noise, And Indoor Air

- Use dust control during demolition, cutting, sanding, and finishing.
- Use HEPA vacuuming or equivalent cleanup where appropriate.
- Coordinate noisy work with building operations.
- Keep waste containers covered and remove debris promptly.

Hazardous Materials

The issued hazardous materials survey reports no asbestos detected in tested samples and no lead detected in tested paint samples. If suspicious material is encountered that is not covered by the report:

1. Stop work in the affected area. 2. Protect the area. 3. Notify Pierce County immediately. 4. Do not disturb the material until the owner gives direction.

Worker Safety Controls

- PPE: safety glasses, gloves, hearing protection, dust protection as task requires.
- Ladders/scaffolds: inspect before use and follow manufacturer requirements.
- Cutting/drilling: control sparks, dust, chips, and noise.
- Manual handling: use team lifts for heavy glass, frames, stone, and stainless.
- Fire/life safety: maintain extinguishers where hot work or spark-producing work is allowed.

Daily Closeout

- Remove debris.
- Vacuum/sweep affected areas.
- Confirm barriers are secure.
- Protect unfinished work.
- Log work completed, inspections, issues, and next-day plan.

Prevailing Wage And Compliance Plan

Purpose

This project appears to be a Washington public works project for Pierce County. The contractor must comply with applicable prevailing wage, certified payroll, responsible bidder, safety, and owner documentation requirements.

Official Rules To Verify Before Submission

- Pierce County prevailing wage monitoring: https://www.piercecountywa.gov/2253/Prevailing-Wage-Monitoring
- Washington L&I prevailing wage lookup: https://www.lni.wa.gov/licensing-permits/public-works-projects/prevailing-wage-rates/index
- Washington L&I worker guidance: https://www.lni.wa.gov/workers-rights/wages/prevailing-wage-rates

Washington L&I guidance states that wage classification depends on the actual work performed, county, and the effective date. L&I also states that the effective date is generally the prime contractor bid due date, or contract award date if award is more than six months after bid due date.

For this bid, use Pierce County and the bid due date of May 20, 2026 unless the bid packet/addendum instructs otherwise.

Likely Trade Classifications To Verify

Do not rely on this list as final classification. Verify through L&I by scope of work.

Work	Likely classification to verify
Selective demolition / labor support	Laborer / Building laborer
Cold-formed metal framing	Carpenter / Drywall installer / Metal stud framer classification as applicable
GWB hanging/taping/finishing	Drywall applicator / Taper classification as applicable
Hollow metal frame installation	Carpenter / Ironworker / Glazier classification depending on actual work and L&I scope
Fire-rated glass installation	Glazier
Granite/terrazzo/tile finish handling	Tile setter / Terrazzo / Marble/stone classification as applicable
Stainless trim install	Sheet metal worker / Carpenter / Glazier depending on scope
Acoustic ceiling repair	Carpenter / acoustical ceiling classification if available
Painting/touch-up	Painter

Contractor Compliance Steps

1. Confirm L&I prevailing wage rates for Pierce County by classification. 2. Include wage, fringe, overtime, and payroll burden in bid labor cost. 3. File Intent to Pay Prevailing Wage if awarded. 4. Post required Intent at the job site if required. 5. Track worker hours by classification and date. 6. Use certified payroll records. 7. File Affidavit of Wages Paid at project completion. 8. Retain payroll and classification support records.

Pricing Warning

If one worker performs multiple classifications and time is not separated correctly, the contractor may need to pay the highest applicable rate for all mixed work. Plan the crew and timesheets carefully.

Background Check Roster

Project: CCB First Floor Door Widening Location: County-City Building, Tacoma, WA Requirement: Background check forms for all workers who may access the site.

Worker Roster

Status	Worker legal name	Company	Role / trade	Phone	Email	Form signed	Submitted	Approved
TODO								
TODO								
TODO								
TODO								
TODO								

Rules

- Include owner, supervisors, employees, subcontractors, delivery/install crews, and anyone who may need site access.
- Use legal names exactly as shown on ID.
- Do not bring unapproved workers to the site.
- Keep copies of submitted forms in the project file.
- Confirm whether Pierce County requires submission before award, before Notice to Proceed, or before site access.

ACM Statement Of Compliance - Draft

This is a working draft. If Pierce County issued an official form, use the official form for signature and upload.

Project: CCB First Floor Door Widening Project No.: 24-00013 Contract No.: SC-2026-SWR-031 Location: County-City Building, 930 Tacoma Ave S, Tacoma, WA 98402

Statement

In accordance with applicable Washington asbestos communication and public works requirements, the undersigned contractor acknowledges receipt and review of the Limited Hazardous Materials Survey Report prepared for the CCB First Floor Door Widening project.

The contractor understands that the report identifies the tested materials and survey findings for the project area. Based on the reviewed report summary, asbestos was not detected in the tested samples and lead was not detected in the tested paint samples. The contractor will communicate the report information to workers and subcontractors before disturbance of affected materials.

If suspect materials are encountered that are not identified in the report, or if concealed conditions differ from the issued documents, the contractor will stop work in the affected area, protect the area, notify Pierce County, and await direction before disturbing the material.

The contractor further agrees to comply with owner procedures, applicable regulations, and safe work practices throughout demolition and construction.

Contractor legal name: _____ Authorized signature: _____ Printed name: _____ Title: _____ Date: _____

Bid Submission Checklist

Project: CCB First Floor Door Widening Solicitation: 2026-SWR-031 Bid due: May 20, 2026, 1:00 PM

Must-Have Upload Items

Status	Item	Owner	Notes
TODO	Completed official bid form from OpenGov/bid packet	Company signer	Use the owner-issued form, not a recreated form.
TODO	Final lump sum bid price	Estimator / owner	Confirm tax treatment: stated budget excludes WA sales tax.
TODO	Bid bond / bid guarantee	Company / surety	Confirm percentage and format in bid packet.
TODO	Signed ACM Statement of Compliance	Authorized signer	Use draft file 09 as working text; sign final owner form if provided.
TODO	Background check forms	Each worker	Include everyone who may enter the site.
TODO	Prevailing wage compliance acknowledgment	Company signer	Confirm classifications and use L&I rates.
TODO	Non-discrimination / responsible bidder certifications	Company signer	Use owner-issued forms.
TODO	Subcontractor list, if required	Company signer	Include glass, hollow metal, drywall/framing, tile/granite, stainless, ceiling.
TODO	Insurance/bonding evidence, if requested	Company / broker	Usually required after award, but prepare now.
TODO	Addenda acknowledgments	Company signer	Check OpenGov on submission day for all addenda.

Technical Attachments To Include If Portal Allows

- Bid cover letter.
- Scope and price proposal.
- Construction schedule and work plan.
- Quality control plan.
- Site safety and logistics plan.
- Prevailing wage and compliance plan.
- Vendor quotes or quote summary if requested or useful.

Hard Stop Checks Before Upload

- 90-minute fire-rated glazing and frames. - Salvage/reinstallation of existing granite/terrazzo. - Public building protection and daily cleanup. - Prevailing wage labor. - Background checks and access logistics. - Permit/inspection coordination. - Closeout and punch list.

- Confirm bid deadline is still May 20, 2026 at 1:00 PM in OpenGov.
- Confirm no addendum changed drawings, glass type, bid form, bond, or due date.
- Confirm bid price covers:
- Submit at least 24 hours early if possible. Do not wait until the last hour.

Final Submission Instructions

Use this as the simple, step-by-step path for the person uploading the bid.

Before Upload Day

1. Open OpenGov Procurement: https://procurement.opengov.com/ 2. Sign in to the company account. 3. Find solicitation 2026-SWR-031. 4. Download every file and addendum again. 5. Compare downloaded files to the bid package we prepared. 6. Fill the official bid form from Pierce County. 7. Fill all required certifications from the official packet. 8. Get the bid bond from surety/bank if required. 9. Upload background check forms if required at bid time. 10. Confirm final price and signer authority.

Upload Package Naming

Use clean names:

- `KNB_Bid_Form_2026-SWR-031.pdf`
- `KNB_Bid_Bond_2026-SWR-031.pdf`
- `KNB_ACM_Compliance_2026-SWR-031.pdf`
- `KNB_Background_Checks_2026-SWR-031.pdf`
- `KNB_Technical_Bid_Package_2026-SWR-031.pdf`
- `KNB_Addenda_Acknowledgement_2026-SWR-031.pdf`

Submission Day: May 20, 2026

Submit before 12:00 PM if possible. Deadline is 1:00 PM.

1. Log in. 2. Open solicitation 2026-SWR-031. 3. Check whether any new addendum was issued. 4. Complete every required online field. 5. Upload required documents. 6. Review every upload. 7. Confirm final bid amount matches the signed bid form. 8. Submit. 9. Save confirmation page/screenshot. 10. Save confirmation email.

Do Not Do

- Do not submit without checking addenda.
- Do not use our draft forms if Pierce County requires official forms.
- Do not leave price blank.
- Do not miss bid bond if required.
- Do not wait until the last 30 minutes.
- Do not include unsupported claims like "asbestos free" beyond what the survey actually tested.

After Submission

- Keep phone/email available for clarification.
- Save all vendor quotes.
- Prepare submittals immediately in case of award.
- Prepare Intent to Pay Prevailing Wage if awarded.
- Keep background-approved crew ready.